

Design Summary	Result
Revision	Rev 01
Calculated Maximum Demand	62.068 kVA
Project Spare Capacity	25%
Design Demand	77.585 kVA
Preliminary Transformer	100 kVA, 11/0.415 kV
Transformer loading at calculated MD	62.01%
Transformer loading incl. design reserve	77.58%
Next verification	Load Flow + voltage drop + motor starting

Load Flow Input Summary	
Office Feeder	P=16.743 kW, Q=5.555 kVAr, S=17.641 kVA, PF=0.949 lagging
Workshoop Feeder	P=36.684 kW, Q=26.036 kVAr, S=44.984 kVA, PF=0.815 lagging
Total:	P=53.427 kW, Q=31.591 kVAr, S=62.068 kVA, PF=0.861 lagging